

**HERITAGE INSTITUTE OF MEDICAL SCIENCES VARANASI****NOTICE OF TENDER**

For Details Please Refer Annexure "A"

1	Tender No.	HIMS /Project/TENDER-1-(2022)-----"D"
2	NAME OF WORKS	Supply and fixing light weight false ceiling - Make; HILUX/AEROLITE or Equivalent
3	Estimated Quantity	50,000 Sqft.
4	Bid type	Single cover system
5	Period of completion	90 Days
6	Cost of tender documents	Nil.
7	Website /Portal address	<a href="http://www.heritageims.com">www.heritageims.com</a>
8	Correspondence	<a href="mailto:heritageims1@gmail.com">heritageims1@gmail.com</a>
9	Type of contract	Item rate contract
10	Information detail	
	a)Bid submission start date	15/09/2022
	b)Last date and time of bid submission	28/09/2022 , 12 Noon
	c)Date and time of bid opening	28/09/2022 , 3.30 PM
11	Eligibility criteria	Have executed similar civil work in recent years, submit list of works done as proof.
12	For all contractors	Contractor will not be allowed to execute the work by subletting or through power of attorney holder on his behalf to a third party/ another firm except son/ daughter of proprietor/ partner/ director and firm's own employee, director, Project manager. This shall be subject to certain conditions which will be prescribed in the Notice Inviting Tender forming part of the tender documents.
	<b>CRITICAL DATES</b>	
13	Publishing date of tender documents	15/09/2022
14	Starting date of tender documents downloading	15/09/2022
15	Clarification start date & time	16/9/2022 , from 3PM to 5.0PM
16	Clarification end date & time	26/09/2022, 3:00PM
17	Pre-bid meeting date & time	NA ( depends on request of venders)
18	Bid documents download end date & time	26/09/2022, 4.00 pm
19	Date and time of 'T' bid ( Technical bid) opening (Cover No 1)	NA
20	Date and time of 'Q' bid opening (Cover No 2-Price Bid)	NA
21	Tender issuing and Accepting Officer	Project Head HIMS Varanasi
22	Executing authority	Project Head HIMS Varanasi
23	Contact No	9140652771, 9602607273
24	<b>Time Schedule</b>	Three months after release of initial advance, further period is negotiable.
25	Notification, additional information, Change ,etc.	Please be in touch with the web site for any UPDATE till date of tender opening
26	Special and General Condition of Contract	Refer Annexure "B" for Special and General conditions, provided separately
	<b>Signature of Contractor</b>	<b>Project Head</b>  <b>Vice Chairman</b> <b>HIMS Varanasi</b>

## Annexure- "A"

Tender No. - HIMS /Project/TENDER-1-(2022)-----"D"

NAME OF WORK: Supply and fixing false ceiling make Hilux/Aerolite or Equivalent.

SI.	DISCRIPATION	A/U	QTY	RATE	AMOUNT
1	Providing and Fixing 15 mm thick densified tegular edged light weight board weighing not less than 5.00 kg/sqm and not more than 5.50 kg/sqm, 100% humidity resistant. While in contact with water do not loose physical integrity, non-combustible as per BS 476, Part-4, eco-friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanizing @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main 'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long drywall screws @ 230 mm interval and laying 15 mm thick densified edges calcium silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanized steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all T sections shall be pre-painted with polyester baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge.	Sqft	50000		
	<b>FLASE CEILING MAKE :- HILUX/AEROLITE CALCIUM SILICATE/ Equivalent WARRENTY :- 10 YEARS</b>				

PM-II

PROJECT MANAGER

HOD (Project)